


GENERAL NOTES

1. Prior to the beginning of demolition activities We shall Ensure that all gas and water piping has been safely shut down or capped off and all piping components have been properly verified, inspected, and labeled. The long island railroad/MTA electricians shall safe-off all existing electrical work and provide temporary lighting and power in the areas as directed by the project manager 20 minutes before and after each work day.
2. In the event torch cutting is required for removals, We shall Provide fire watch and smoke eaters with HEPA Filters during any torch cutting activity that takes place within the structure
3. Temporary water, electrical and sanitary facilities shall be provided and maintained through-out the entirety of the project.
4. All Demolition work shall be executed by skilled professionals with a minimum 5years experience in project of similar size and scope
5. a Minimal 5'0" clearance shall be mainatined from the inner most curb or obstruction(i.e. parking meters) and outermost section of barricade walls.

 indicates area of terrazzo floor to be protected during construction

Signage Schedule

Key	Message	Size
1	← "Long Island RailRoad field Office"	2'high X 4' Wide
2	← "CNA Enterprises field Office"	2'high X 4' Wide
3	"This work is part of the MTA's Capitol Program for the Long Island Rail Road to restore the system to a state of good repair. We hope that you will bear with us and forgive any inconvenience while work is in progress."	2'high X 4' Wide
4	Railroad Issued Project Identification sign	3'high X 4' Wide

TEMPORARY DOOR SCHEDULE

Key	Description	
1	Pair - (2) 3'0 X 7'0 Hollow metal Doors & Frame with Mortise lock and Padlock Hasp	
2	Single (1) 3'0 X 7'0 Hollow metal Door & Frame with Mortise lock and Padlock Hasp	
3	NOT USED	

BARRICADE SCHEDULE

Key	Desciption	
A	2X4X8'-10' Pressure Treated Studs with 3/4" Marine Plywood sheathing (1) side @ wall and roof sections	
B	Same as "A" with no Roof	

KEY NOTES

- D01 REMOVE PERFORATED METAL HUNG CEILING, INSULATION AND HANGERS.
- D02 REMOVE FLOOR FINISH AND SUBFLOORING MATERIALS DOWN TO EXIST. CONC. SLAB INCLUDING BUT NOT LIMITED TO CERAMIC FLOOR TILE, VCT AND CARPET. PATCH CONC. SLAB, CLEAN AND LEVEL TO ACCEPT NEW FLOOR FINISHES AS INDICATED ON CONTRACT DOCUMENTS AND AS RECOMMENDED BY MANUFACTURER.
- D03 REMOVE CMU BLOCK WALL FROM FLOOR SLAB TO ROOF SLAB.
- D04 REMOVE HOLLOW METAL DOOR, FRAME AND HARDWARE.
- D05 REMOVE ENTIRE MTL. STUD/ GYPSUM WALL BOARD, RUNNERS AND WIRE MOULDING. REMOVE WOOD COUNTER AND WINDOWS IN WALL.
- D06 REMOVE TICKET COUNTER, STEEL ROLL-UP WINDOW AND FRAME.
- D07 REMOVE CMU BLOCK WALL FROM EXIST. CONC. FLOOR SLAB TO 8'-0" HIGH. PROVIDE TEMPORARY SUPPORT OF EXIST. WALL TO REMAIN AND PREP FOR INSTALLATION OF NEW DOOR OPENING.
- D08 REMOVE 6' HIGH PARTITION WALL.
- D09 CAREFULLY REMOVE BUST OF NORMAN LEVY AND TURN OVER TO MTA POLICE FOR STORAGE.
- D10 REMOVE 1'X4' RECESSED FLUORESCENT CEILING LIGHTS AFTER LIRR EL&P HAS PROVIDED DISCONNECTS. SEE ELECTRICAL DRAWINGS.
- D11 REMOVE TOILETS, SINKS, GRAB BARS, MIRRORS, TOILET ACCESSORIES AND OTHER PLUMBING FIXTURES. CAP, RELOCATE OR PREPARE EXIST. PIPING FOR NEW FIXTURES. SEE PLUMBING DRAWINGS.
- D12 REMOVE ALL MECHANICAL HVAC EQUIPMENT (DUCTS, HANGARS). SEE MECHANICAL DRAWINGS.
- D13 MAINTAIN EXIST. TERRAZZO FLOORING. IF TERRAZZO IS FOUND BELOW EXIST. CARPETING, CAREFULLY REMOVE CARPET AND ADHESIVE TO EXPOSE EXIST. TERRAZO FLOORING. PROTECT IN PLACE DURING DEMOLITION. CLEAN AND POLISH ENTIRE AREA.
- D14 REMOVE WALL TILES BACK TO EXIST. CMU BLOCK WALL. CLEAN AND PREP CMU FOR FINISH WALL MATERIAL.
- D15 REMOVE MOP SINK AND ASSOCIATED PLUMBING
- D16 REMOVE WOOD PANELING & SHELVING BACK TO CMU WALL. PATCH HOLES WITH GROUT. PREP CMU WALL FOR FINISH MATERIALS AS RECOMMENDED BY WALL FINISH MATERIALS MANUFACTURER.
- D17 REMOVE EXTERIOR STOREFRONT DOOR AND DOOR FRAME. TURN OVER EXISTING DOOR TO LIRR.
- D18 EXISTING WINDSCREEN TO REMAIN.
- D19 REMOVE A.C. UNIT.
- D20 REMOVE LOUVERS AND PATCH HOLES IN CMU. PREP WALL FOR FINISH MATERIAL AS RECOMMENDED BY WALL FINISH MANUFACTURER.

CNA
enterprises, Inc.

Demolition Removals and Salvage Plan

MTA Police Facility at Merrick Station

Drawn by: **Mark Tarver**

Date: **6/10/2010**
6/11/2010

DM-1

SCALE
1/4" = 1'-0"

CNA Enterpirse, Inc
33-56 11th Street
Long Island City 11106
phone 718-533-8181
fax 718-533-8225

1 Typical Barricade Type "A"
NTS

